

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	(IRON COUNTY) LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>41</u> <sup>N.</sup> <del>S.</del> , R. <u>32</u> <sup>E.</sup> <del>W.</del>	K-3
2. PROPERTY CONTROLLING IN SECTION <u>11</u>	, T. <u>41</u> <sup>N.</sup> <del>S.</del> , R. <u>32</u> <sup>E.</sup> <del>W.</del>	2 & 7
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ <sup>N.</sup> <del>S.</del> , R. _____ <sup>E.</sup> <del>W.</del>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 2, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**Corner K3 (Section Corner 1, 2, 11, & 12, T41N, R32W):**  
 Hemlock post (Not found. Found WMPC monument in place.)  
 Y. Birch 16 S81W 18 (Not found. No subsequent accessories found.)  
 Elm 22 N32E 25 (Not found. No subsequent accessories found.)

**Corner 2 (East 1/16 corner between Sections 2 & 11, T41N, R32W) and**

**Corner 7 (North 1/16 corner between Sections 11 & 12, T41N, R32W):**  
 Neither of these corners set in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**Corner K3:** WMPC notes indicate mon. was set at record distance N of a possible original 1/4 cor. to S, and that no original or other evidence was found. The mon. actually is N0°10.4'W 40.030 ch. from the 1/4 cor., but is also S89°51.2'E 80.072 ch. from a probable original cor. to W, so it is probably satisfactory in the absence of better evidence.

**Corner 2:** Established on line between Sec. Cor. 20.018 ch. E and 1/4 cor. 20.018 ch. W.

**Corner 7:** Established on line between Sec. Cor. 20.015 ch. N and 1/4 cor. 20.015 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Corner K3:** WMPC concrete tetrahedron with 3" x 3" sq. brass marker  
 Sugar Maple 5 N88°W (mag.) 27.4 ft. "S2, NBT"  
 Basswood 6 S87°E (mag.) 12.6 ft. "S12, NBT"  
 Y. Birch 6 N31°E (mag.) 10.0 ft. "S 1, NBT"      Declination is 0°10' West.

**Corner 2:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 Sugar Maple 10 S22°E (mag.) 30.0 ft. "1/16S, BT"  
 Red Maple 9 N34°E (mag.) 15.0 ft. "1/16S, BT"      Declination is 0°15' East.

**Corner 7:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap  
 Sugar Maple 7 N48°E (mag.) 29.7 ft. "1/16S, BT"  
 Sugar Maple 6 S 1°E (mag.) 13.8 ft. "1/16S, BT"      Declination is 0°30' West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE January 10, 1979  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

