



CORNER RECORDATION CERTIFICATE

REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

LOCATED IN--:

CORNER CODE NUMBER

1. PUBLIC LAND SURVEY _____ T. _____ N. _____ S., R. _____ E. _____ W. _____
2. PROPERTY CONTROLLING IN SECTION 11 , T. 41 N. X, R. 32 X W. _____
14a & 16a
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. _____ S., R. _____ E. _____ W. _____
4. LOT NO. _____ , RECORDED PLAT _____
5. PRIVATE CLAIMS _____

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 3, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 14a (Meander Corner between Sections 11 & 12, T41N, R32W):
 Black Ash 6 for corner (Not found. No subsequent monuments found.)
 No witnesses (Not found. No subsequent accessories found.)

Corner 16a (Meander Corner between Sections 11 & 14, T41N, R32W):
 No monument indicated (No subsequent monuments found.)
 B. Ash 12 S80W 61 (Not found. No subsequent accessories found.)
 Maple 16 N82W 80 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner: Corner 14a:
 Restored on N bank of Brule River on S'yly extension of true line bet. 1/4 cor. bet. Sec. 11 & 12 and a 1 1/4" I.D. iron pipe found on a terrace above the river bank proper and presumed to represent either the M.C. or a property line. M.C. as reported herein bears S0°31.4'W 26.095 ch. from the 1/4 cor. and is about 7.5 ft. N of water's edge.

Corner 16a: Restored on N bank of Brule River on E'yly extension of true line bet. Sec. Cor. 10, 11, 14, & 15 and 1/4 cor. bet. Sec. 11 & 14 and a probable line tree stump 17.441 ch. W of the M.C., said line bearing N89°46.1'E. Original M.C. probably was about 6.0 ft. farther east, but I set the new mon. about 8 ft. in from water's edge for better protection.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner 14a: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 1 1/4" I.D. iron pipe N0°31.4'E (true) 42.0 ft.
 B. Ash 7 N79°W (mag.) 24.9 ft. "MC, NBT"
 Declination is 0°35' East.

Corner 16a: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 B. Ash 12 N47°W (mag.) 49.2 ft. "MC, NBT"
 B. Ash 8 S77°W (mag.) 57.7 ft. "MC, NBT"
 Declination is 0°15' East.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 20, 1979
 CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

