

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. R. 32 W.	J-5
2. PROPERTY CONTROLLING IN SECTION 11	T. 41 N. R. 32 W.	15
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. S. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner J5 (1/4 corner between Sections 11 & 14, T41N, R32W):
 Cedar post (Not found. No subsequent monuments found.)
 W. Pine 16 S58W 35 (Not found. No subsequent accessories found.)
 W. Pine 24 N3E 14 (Not found. No subsequent accessories found.)

Corner 15 (West 1/16 corner between Sections 11 & 14, T41N, R32W):
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner J5: Restored 11/28/77 proportionately on line between Sec. Cor. S89°46.1' W 39.971 ch. and a probable W. pine line tree stump N89°46.1' E 10.892 ch. Severe forest fires in the past have burned up most of the pine stumps in the vicinity of the 1/4 corner, and I could not find any possibly identifiable stumps of the original BT's. Corner falls on S side of a hill as recorded in the original field notes.

Corner 15: Established 11/30/77 on line between Sec. Cor. 19.9855 ch. W and 1/4 cor. 19.9855 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner J5: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 ⊙ Chiselled in a boulder N56°W (mag.) 14.7 ft.
 Elm 11 (may be dead) S71°W (mag.) 40.2 ft. "1/4S, NBT"
 Declination is 0°40' East. Distances are horizontal.

Corner 15: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Cedar 12 N54°W (mag.) 16.9 ft. "1/16S, BT"
 Cedar 10 S34°E (mag.) 37.4 ft. "1/16S, BT"
 Declination is 0°15' East.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 1978
CHIEF OF SURVEY PART
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

