

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(IRON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. <u>X</u> , R. <u>32</u> <u>X</u> W.	K-4
2. PROPERTY CONTROLLING IN SECTION <u>15</u>	, T. <u>41</u> N. <u>X</u> , R. <u>32</u> <u>X</u> W.	7a
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 2, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner K4 (1/4 corner between Sections 11 & 12, T41N, R32W):**
 Hemlock post (Not found. Found WMPC monument in place.)
 W. Pine 22 S64W 17 (Probably found. No subsequent accessories found.)
 Sugar 16 N36E 27 (Not found. No subsequent accessories found.)
- Corner 7a (Meander Corner between Sections 14 & 15, R41N, R32W):**
 Cedar post (Not found. No subsequent monuments found.)
 Cedar 10 N63W 20 (Possibly found. No subsequent accessories found.)
 Fir 6 N65E 14 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner K4:** WMPC notes indicate mon. was set from stump of possible original W. Pine 22 S64W 17. There is a rotted W. Pine stump at that position, which lies on top of a hill with the land descending southward, conformable to the original field notes. I conclude that the corner position is probably original as it is consistent with other original evidence found in adjacent sections.
- Corner 7a:** Restored at record distance S of mon. at Sec. Cor. 10, 11, 14, & 15 on extension of true sec. line bet. Sec. 10 & 11. From this position, a burned cedar stump bears N69°W 18 lks., possibly an original BT, which the record indicates was N63°W 20 lks. from the M.C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner K4:** WMPC concrete tetrahedron with 3" x 3" sq. brass marker
 Red Maple 6 N36°E (mag.) 27.8 ft. "1/4S, NBT"
 Red Maple 6 S55°E (mag.) 17.6 ft. "1/4S, NBT"
 Declination is 0°35' East.
- Corner 7a:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap
 B. Ash 7 N89°W (mag.) 11.1 ft. "MC, NBT"
 Cedar 9 N11°E (mag.) 31.6 ft. "MC, NBT"
 Declination is 0°40' East.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 20, 1978

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

