

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Iron  
(County)

Located In:

Corner Code -##

1. Public Land Survey	T 41N R32W	K1
	T _____ R _____	L1
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S 1 T _____ R _____	2
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12							
5													
6	15	16	17	18	19	20	21	22	23	24			
7													
8	19	20	21	22	23	24							
9													
10	29	30	31	32	33	34	35	36					
11													
12	31	32	33	34	35	36							
13													

I, Keith Sackett, in a field survey on October 14, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


K1	L1	2
Original monument and accessories not found. Found Wisconsin-Michigan Power Co. monument.	Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K1	L1	2
Restored at WI-MI Power Co. monument.	Restored midway on line.	Established midway on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K1	L1	2
WI-MI Power Co. monument.	Set 1" I.B. x 32" I.P. w/4" aluminum cap.	Set 1" I.B. x 32" I.P. w/4" aluminum cap.
10" maple 882N 33.9' B2 NBT	11" basswood 887W 15.4' 1/4S NBT	13" hemlock N63E 15.8' 1/16S BT
8" cherry 876E 7.5' S1 NBT	14" sugar N66E 15.6' 1/4S NBT	12" hemlock 886W 37.0' 1/16S BT
8" cherry 859W 16.2' B2 NBT	16" sugar 804E 20.1' 1/4s NBT	BT
	4" maple 8E 4" squared.	12" hemlock 861E 38.5' 1/16S BT



Signed by Keith Sackett Date 2-26-88

Surveyor's Michigan License No. 19006