

**SURVEY &
REMONUMENTATION**

FEB 21 2001

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

COMMENCING YEAR 2000
RECEIVED FOR RECORD
IRON COUNTY, MICHIGAN

00 DEC 22 PM 3: 27

L.C. Records: L. 8, P. 3024
Edwin [Signature]
REGISTER OF DEEDS

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>31W</u> T <u>42N</u> R <u>31W</u> T _____ R _____ T _____ R _____	<u>C.D-13e (012)</u> <u>C.D-1e (002)</u> _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____ _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

East Meander Corner to Section 32, T43N, R31W
East Meander Corner to Section 5, T42N, R31W

I, Gary L. Pisoni, in a field survey on November 28, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on July 30, 1846 by John Burt, U.S. Deputy Surveyor.
Original Corner; 10" Black Ash Meander Corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

Corner located on the East bank of the Michigan River and is 8' from waters edge.

Restored the corner position by single proportionate measurement and set a witness corner meander corner on line between the Southwest Section corner and the South quarter corner of Section 32.

Corner record research on file with County Representative.

PEER GROUP APPROVED
[Signature]
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, set a 5/8" diameter by 30" long rebar pin with a 3" diameter aluminum cap stamped as follows: Iron County Remonumentation, T43N, R31W, W.C.M.C., S- 32, S-5, T42N, S 89° 46'14"W, 48.12 feet, 2000, RLS 27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

White Pine	9"	N 17° W	16.27 feet
Red Pine	9"	S 30° E	30.22 feet
Red Pine	10"	S 28° W	6.01 feet
Steel sign post		N 80° E	0.6 feet

00-092
Signed by *Gary L. Pisoni* Date 12-19-2000

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971
No. 27457
REVISOR MAY 12, 1975
REVISOR JAN 1983
REVISOR OCT. 1995

