

**SURVEY & REMONUMENTATION**

FEB 21 2001

COMMENCING YEAR 2000  
RECEIVED FOR RECORD  
IRON COUNTY, MICHIGAN

00 DEC -5 PM 12:49

L.C. Records. 18, P. 196

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*Robert A. Goodreau*  
REGISTERED PROFESSIONAL SURVEYOR

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 31W T 42N R 32W T ___ R ___ T ___ R ___	A-5 ✓ M-5 _____ _____
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert A. Goodreau in a field survey on March 22, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-5 Original corner established by William Burt, U.S. Deputy Surveyor, on 31 July 1846

Original witnesses: S. Pine 10 N64W 17 links  
W. Pine 5 S83E 25 links

2.5" ID iron pipe set 2653' West and 5280' North of established corners by Murray Yates RLS in 1953 (Liber 2, Page 21), and described by Keith L. Sackett RLS on 16 August 1985 (Liber 5, Page 106).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5 Found corner as described by Sackett.

Found witnesses recorded by Sackett as: 12" Jack Pine S64W 2.5 ft. S13, NBT  
12" Red Pine N60W 11.4 ft. S12, NBT  
4" Jack Pine N18E 6.9 ft. S7, NBT

Corner record research on file with county representative.

PEER GROUP APPROVED  
*Iron County Records 11-14-2000*  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5 Accepted corner as found.

Witnesses: Set 16d nails in above bearing trees at recorded distances.  
5/8" iron pin w/ 3.5" aluminum remon. cap South 2.00'  
Sign post South 2.50'

Signed by *Robert A. Goodreau*  
Surveyor's Michigan License No. 43053

Date July 1, 2000

