

**SURVEY & REMONUMENTATION**

FEB 21 2001

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>31W</u>	E-13
	T <u>42N</u> R <u>31W</u>	E-11 ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

COMMENCING YEAR 2000  
RECEIVED FOR RECORD  
IRON COUNTY, MICHIGAN  
00 DEC -8 PM 1:05  
L.C. Records, L.S., P. 270  
*Gary L. Pisoni*  
REGISTERED AS SURVEYOR  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner to Sections 32 and 33, T43N, R31W  
Section Corner to Sections 4 and 5, T42N, R31W

I, Gary L. Pisoni, in a field survey on November 10, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on July 30, 1846 by John Burt, U.S. Deputy Surveyor.  
Original Corner; Hemlock Post  
Original Bearing Trees:  
White Pine 18" N 21° E 34 links (22.44 feet)  
White Pine 18" N 48° W 35 links (23.10 feet)  
On August 7, 1849, John Burt, U.S. Deputy Surveyor established the following new bearing trees:  
White Pine 24" S 55° W 10 links (6.60 feet)  
White Pine 24" S 44° E 48 links (31.68 feet)

PEER GROUP APPROVED  
*Iron County from 11-20-2000*  
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.  
Found a W/MI Power Co. Concrete monument with a brass cap marking corner position, 12" above ground surface and stamped as follows: T43N, R31W, S-32, S-33, S-5, S-4, 6/30/43, L.Ledug, A.E.Ebel. I accept the concrete monument as the best available evidence for restoring the corner position.  
Monument is 22' North of an East/West woods road.  
Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)  
Oak 16" North 45.77 feet  
White Pine 24" S 69° E 28.21 feet  
White Spruce 9" S 23° E 4.61 feet  
Steel sign post N 58° E 1.1 feet

00-038  
Signed by Gary L. Pisoni Date 11-13-2000  
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS  
REGISTERED SURVEYOR  
STATE OF MICHIGAN  
GARY L. PISONI  
LAND SURVEYOR  
No. \_\_\_\_\_  
REVISED JAN. 1983  
REVISED OCT. 1996