

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____	_____
	S <u>34</u> T <u>42N</u> R <u>31W</u>	9	_____
	S <u>34</u> T <u>42N</u> R <u>31W</u>	6	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	_____
	S ___ T ___ R ___	_____	_____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Apr 12 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (9-Sec. 34) East 1/16 corner, Section 34. Not established in the original survey.
- (6-Sec. 34) Northeast 1/16 corner, Section 34. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (9-Sec. 34) Established the corner midway and on a straight line between Center of Section (unmonumented) 1313.79' West and I12 1313.79' East.
- (6-Sec. 34) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| (9) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Blazed, scribed, and set
measuring nails in:
4" Balsam N52E 6.7' "1/16S BT"
8" W.Spruce S50E 23.8' do
3" W.Spruce S03E 15.1' do
8" Balsam N27W 14.7' do
Bearings are magnetic. Distances are to
nail with tag. | (6) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Blazed, scribed, and set
measuring nails in:
6" J.Pine N04E 15.12' "1/16S BT"
4" Spruce N28E 27.30' do
8" Spruce S20W 60.18' do
6" Spruce S76W 54.24' do
Bearings are magnetic. Distances are to
nail with tag. |
|--|---|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 5/25/04

For the Michigan Department of Natural Resources, Office of Land and Facilities