

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> <small>(County)</small>	Located in:	Corner Code #	
1. Public Land Survey	T <u>42N</u> R <u>31W</u>	<u>84</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	<u>8</u>	
	S <u>7</u> T <u>42N</u> R <u>31W</u>	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Feb 09 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (84) Center of Section 7. Not established in the original survey.
- (8-Sec. 7) West 1/16 corner, Section 7. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (84) Recovered a 1" square iron pin, projecting 3.5" above ground, in accord with monumentation recovered along the south line of the RICHARDS unrecorded plat to the east. This pin has apparently been long used as the Center of Section 7 and as I find it to be only 2.97' south and 8.73' east of the intersection of the Quarter lines of Section 7, I accept it as a careful and faithful determination of the position of the corner.
- (8-Sec. 7) Established the corner 20 chains, proportionate to the original record, west of the Center of Section 7, and on a straight line between the Center of Section 7 and the West 1/4 corner of Section 7. Center of Section 7 is 13317.61' East and West 1/4 corner is 1321.56' West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |   |
|--|---|
| (84) Found 1" square iron pin. Set measuring nails in:                               | (8) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:        |
| 8" R.Pine N75E 23.8'      mrkd "C1/4 BT"   | 8" dbl R.Pine N62E 49.7'      mrkd "1/16S BT"                                   |
| 15" dbl R.Pine S59E 15.1'      do  | 14" dbl R.Pine S12E 12.8'      do   |
| 12" dbl R.Pine S26W 25.0'      do  | 21" R.Pine N77W 33.0'      do   |
| 5" R.Pine N38W 9.2'      do  | 13" J.Pine N36W 22.4'      do   |
| Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | Bearings are magnetic. Distances are to nail with tag. Set cedar post adjacent. |



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 4/5/05

For the Michigan Department of Natural Resources, Office of Land and Facilities