

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| Iron _____ (County) | Located In: | Corner Code # |
|---------------------------------------|-----------------------------------|---------------|
| 1. Public Land Survey | T <u>42N</u> R <u>31W</u> | <u>62</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T <u>42N</u> R <u>31W</u> | <u>9</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims | | |

Register of Deeds Stamp & File
Number

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | ● | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

Nov 09 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G2) Quarter corner common to Sections 3 and 4. 2000 - Recorded in Liber 8 LCR Page 203 by R.A. Goodreau PS. Found 1"IDx36" I.pipe with 3.5" aluminum cap by A.O. Enger RLS. 14" Spruce S64E 34.64', 14" Spruce S19W 9.35', 4" Balsam Fir S88W 19.4', 6" Cedar N82E 53.35', sign post 1' south.
 (9-Sec. 4) East 1/16 corner, Section 4. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G2) Recovered the monument of record in good condition and at record bearing and distance from the 2000 witnesses of record. The 14" Spruce S64E is windthrown and the Cedar N82E has been cut down. Left the monument in place and made two new accessories, as described below.
 (9-Sec. 4) Established the corner midway and on a straight line between Center of Section 1318.50' west and Quarter corner 1318.50' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | |
|---|--|
| (G2) Found 1"ID I.pipe with 3.5" alum. MDNR cap. Set measuring nails in: 5" Spruce N23W 6.7' mrd "1/4S NBT" 3" Spruce East 13.8' do Found existing measuring nail in: 14" Spruce S22W 9.35' old blazes 6" Balsam N89W 19.4' do Bearings are magnetic. Distances are to nail with tag. | (9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 8" Spruce N67E 32.5' mrd "1/16S BT" 6" B.Spruce N02W 42.9' do 11" Spruce S29W 33.8' do 4" Spruce N52W 53.9' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|---|--|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/13/06

For the Michigan Department of Natural Resources, Office of Land and Facilities