

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S <u>7</u> T 42N R 31W	4
	S <u>7</u> T 42N R 31W	5
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

Feb 09 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(4-Sec. 7) Northwest 1/16 corner, Section 7. Not established in the original survey.

(5-Sec. 7) North 1/16 corner, Section 7. Not established in the original survey. Noted on surveys previously made by D.Lappala in Oct. 1979 (Liber 202 Page 194) and R.F.Perkins PS12027, Sept. 1998, for "Robert Flood Lands", no recording information available. In the 1979 survey, the corner is shown marked by an iron pin or pipe [not legible]. In the 1998 survey, it is shown marked by an iron pipe. In both cases, the monument shown as the corner was used to control the south line of Government Lot 1, Sec. 7. In the parcel descriptions created by the 1998 survey, it is described as an "existing iron pipe Occupied One-Sixteenth Corner...thence...East along the Occupied South Line of Government Lot One...etc. A local land-owner in G.L. 1 told me he regards this pipe as marking his land title corner.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(4-Sec. 7) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

(5-Sec. 7) Found a 3/4" iron pipe with plumbing hardware affixed to top, 26.1' South and 8.5' East of the proper position for the corner, which I subsequently established and monumented at a position midway and on a straight line between the North 1/4 corner of Section 7 and the Center of Section 7 1340.72' north and south. I did not accept the pipe as marking the North 1/16 corner of Section 7, though it may control title to certain lands to the East.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:	(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
3" J.Pine S60E 7.8'    mrkd "1/16S BT"	8" J.Pine N84E 4.0'    mrkd "1/16S BT"
14" R.Pine S87W 32.8'    do	8" J.Pine S07W 23.7'    do
4" J.Pine N57W 1.4'    do	9" J.Pine S65W 16.4'    do
14" R.Pine N06W 40.6'    do	8" J.Pine N71W 12.8'    do
Bearings are magnetic. Distances are to nail with tag. Set cedar post adjacent.	Found 3/4" I.pipe S18E 27.5' Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 4/5/05