

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>4</u> T <u>42NR 31W</u>	<u>1</u>
	S <u>4</u> T <u>42NR 31W</u>	<u>5</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Nov 06 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (1-Sec. 4) West 1/16 corner between Section 4 T42N-R31W and Section 33 T43N-R31W. Not established in the original survey.
- (5-Sec. 4) North 1/16 corner Section 4. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (1-Sec. 4) Established the corner midway and on the township line between Section corner 1320.98' west and Quarter corner 1320.98' east.
- (5-Sec. 4) Established the corner at 20.00 chains, proportionate to the original record (parenthetical), north of the Center of Section 4, on the N-S 1/4 line. The position for the corner is 1335.03' north of the Center of Section and 1301.31' south of the Quarter corner on the north line of Section 4.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (1) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
7" Spruce N37E 44.4' mrkd "1/16S BT"
2" Spruce S48E 16.9' do
8" Spruce S41W 10.7' do
2" Poplar N65W 9.7' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | (5) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
3" Spruce N72E 10.7' mrkd "1/16S BT"
4" twin Spruce N13W 13.6' do
4" Spruce S78E 37.8' do
5" Spruce S70W 26.4' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|--|--|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/13/06