

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T 42N R 31W	E11
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 28 T 42N R 31W	F10
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Stephan J. Szyszkoski, in a field survey on F10 10/13/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(E11) Corner common to Sections 28-29-32-33. 2002 - Gary L. Pisoni RLS found Wisconsin Michigan Power Company concrete monument with brass tablet affixed and accepted same. Red Maple 12" N31E 93.99', Dbl Red Maple 8" S49E 58.70', Steel sign post East 2.90', Triple Maple 12" N83E 51.80', Maple 10" S18E 32.40', W.Birch 8" S25W 26.50'. Recorded in Liber 9 of LCRC Page 275 for Iron Co. Survey and Remonumentation.

(F10) Center of Section 28. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(E11) The monument of record was found disturbed and out of position, on the eastern shore of Peavy Pond. The monument has apparently been displaced by wave and/or ice action. Reestablished the record position for the corner and established a WITNESS CORNER 17.00' east of the corner position and on the Section line between Sections 28 and 33. The Witness Corner cap is stamped appropriately, indicating that the corner position is 17.00' West.

(F10) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(E11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap on the Sec. Line 17.00' East of the cor. position. Made new measurements to the witnesses of record from this Witness Corner monument.  
 10" Maple N24E 89.2' nail & tag w/poster  
 9" triple Maple N78E 38.1' do do  
 8" Dbl Maple S40E 47.5' do do  
 12" Maple in clump S10W 29.8' do do  
 Steel sign post moved to 1.1' W'ly  
 Bearings are magnetic.

(F10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 10" W.Spruce N57E 8.5' mrkd "C1/4 BT"  
 10" Maple in clump S53E 13.5' do  
 4" Poplar S29W 21.8' do  
 5" Sugar N21W 30.6' do  
 Set sq'd cedar post adjacent.  
 Bearings are magnetic.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 11/03/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

