

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 28 T 42N R 31W	8
	S 28 T 42N R 31W	11
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 11 10/13/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- (8-Sec. 28) West 1/16 corner, Section 28. Not established in the original survey.
- (11-Sec. 28) Southwest 1/16 corner, Section 28. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (8-Sec. 28) Established the corner midway and on a straight line between Quarter corner 1307.55' West and the Center of Section 28 1307.55' East.
- (11-Sec. 28) Established the corner at the intersection of staight lines connecting opposite 1/16 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |  |   |
|--|---|
| (8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.<br>Set measuring nail with MDNR tag in the side of:<br>6" Maple N37E 27.8' mrkd "1/16S BT"<br>10" Maple S66E 23.5' do<br>4" W.Spruce S01W 22.6' do<br>13" Maple N44W 14.6' do<br>Set sq'd cedar post adjacent.<br>Bearings are magnetic. | (11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.<br>Set measuring nail with MDNR tag in the side of:<br>4" Poplar S36E 3.6' mrkd "1/16S BT"<br>4" B.Spruce S28W 23.9' do<br>12" Maple N48W 8.4' do<br>7" Maple N11W 45.7' do<br>Set sq'd cedar post adjacent.<br>Bearings are magnetic. |
|--|---|

Signed by Stephan J. Szyszkoski Date 11/03/2009  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

