

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 31W	K9
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T 42N R 31W	13
	S 23 T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 13 10/14/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K9) Corner common to Sections 23-24-25-26. 2002 - Corner recovered for Iron County Survey and Remonumentation by Gary L. Pisoni RLS and recorded in Liber 9 of LCRC Page 314. Found 1"IDx36" iron pipe with 4" alum. MI Dept. of Conservation cap. 2002 witnesses: Sugar 8" N02E 26.65', Sugar 6" S23E 24.87', Maple 8" N83E 35.15', Spruce 14" S68W 24.17', Steel sign post N59W 1.82'.

(13-Sec. 23) Southeast 1/16 corner, Section 23. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K9) Recovered the monument as described, in good condition, and at record bearing and distance from 4 of the 5 witnesses in the 2002 record. Left the monument in place and added one new bearing tree.

(13-Sec. 23) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K9) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Found measuring nail in:
 9" Sugar N03E 26.65' old blazes
 9" Sugar N85E 35.15' do
 7" Sugar S21E 24.87' do
 Set measuring nail with MDNR tag in the side of
 10" Sugar N58W 27.15' mrkd "S23 NBT"
 Steel sign post N57W 1.82'
 Bearings are magnetic.

(13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 12" Cedar N55E 20.4' mrkd "1/16S BT"
 6" B.Ash S34E 33.3' do
 12" Cedar N77W 18.45' do
 13" Y.Birch N40W 18.35' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/03/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

