

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u>	Located In:	Corner Code #	
(County)			
1. Public Land Survey	T 42N R 31W	J9	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T 23 R 42N R 31W	14	
	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 14 10/14/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(J9) Quarter corner common to Sections 23 and 26. 2002 - Gary L. Pisoni RLS remonumented the corner for Iron County Survey and Remonumentation. Set 5/8" dia.x30" rebar with a 3" aluminum cap. Basswood 10" S16E 16.48', Sugar 9" N75W 17.71', Maple 7" S80E 7.94', Basswood 14" S55W 2.72', Steel Sign post South 0.67'. Corner recorded in Liber 9 of LCRC, Page 311.

(14-Sec. 23) South 1/16 corner between Sections 23 and 24. 1974 - A.O.Enger RLS established the corner on line between Section corner 20.055 ch. south and Quarter corner 20.055 ch. north. Set 1"IDx36" I.pipe with 3.5" aluminum State of Michigan cap. Hemlock 16" S54E 27.8', W.Pine stump 19" N59E 5.5'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(J9) Found a 5/8" dia. rebar, uncapped, in good condition, at record bearing and distance from 4 of the 5 witnesses noted in the 2002 record. Left the monument as found and marked a new bearing tree as described below.

(14-Sec. 23) Found the 1974 monument in good condition and at record bearing and distance from the 1974 Hemlock BT, in good condition, and the W.Pine stump, in poor shape. Verified the position of the monument and accepted same as a careful and faithful establishment of the position of the corner.


**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(J9) Found 5/8" dia. rebar, no cap. Found meas. nail in the side of:  
 7" Sugar S80E 7.95' old scribing  
 9" Basswood S15E 16.5' overgrown blazes  
 10" Sugar N73W 17.7' do  
 Set measuring nail with MDNR tag in the side of  
 10" Maple N10E 53.9' mrkd "1/4S NBT"  
 Steel sign post found S11W 0.67'  
 Bearings are magnetic.

(14) Fd. 1"ID I.pipe with 3.5" alum. cap. Set measuring nail with MDNR tag in the side of:  
 18" Hemlock S48E 28.15' old blazes 1974 BT  
 13" Cedar S25E 24.7' mrkd "1/16S BT"  
 11" Sugar S19W 9.45' do  
 11" Maple N75E 13.95' do  
 Fd. sq'd cedar post adjacent.  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 11/03/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities