

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 19 T 42N R 31W	6
	S 19 T 42N R 31W	11
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 11 04/22/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(6-Sec. 19) Northeast 1/16 corner, Section 19. Not established in the original survey.

(11-Sec. 19) Southwest 1/16 corner, Section 19. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(6-Sec. 19) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

(11-Sec. 19) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The position for the corner was not monumented. Established a Witness Corner on the E-W 1/16 line 426.49' west of the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 8" Maple N83E 9.65' mrkd "1/16S BT"  
 9" W.Spruce S20W 5.3' do  
 4" R.Pine S63W 4.1' do  
 3" Maple N20W 6.7' do  
 Set sq'd cedar post adjacent.  
 Bearings are magnetic.

(11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap  
 for a witness corner 426.49' west of the corner  
 position. Set measuring nail with MDNR tag in  
 the side of:  
 6" Spruce N30E 18.2' mrkd "WC BT"  
 10" Oak S70E 25.7' do  
 3" Spruce S05W 11.2' do  
 7" Poplar S53W 24.5' do  
 Set post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 05/06/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division