

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S <u>6</u> T <u>42N</u> R <u>31W</u>	<u>13</u>	<u>C-N-SE 1/64</u>
	S <u>6</u> T <u>42N</u> R <u>31W</u>	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 04/07/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(13-Sec. 6) Southeast 1/16 corner, Section 6. Not established in the original survey. The South E-W 1/16 line of Section 6 was monumented in 1959, being the north line of the Martinson-Shemky Subdivision, Liber 3 of Plats, Page 25, Iron County Records.

(C-N-SE 1/64, Sec. 6) 1/64 corner south of 1/16 corner #9, being the SE corner of the N1/2 of the NW1/4 of the SE1/4 of Section 6. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(13-Sec. 6) Established the corner at the intersection of the North line of the Martinson-Shemky subdivision, as monumented, with the East N-S 1/16 line of Section 6. Said 1/16 line is a line originating at the East 1/16 corner of Section 6 and running southerly at a bearing which is the mean bearing of the East line of Section 6 and the N-S 1/4 line of Section 6.

(C-N-SE 1/64, Sec. 6) Established the corner midway and on a straight line between 1/16 corner #9 and 1/16 corner #13, 666.31' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" twin Maple N44E 19.9' mrkd "1/16S BT"
 18" R.Pine S08W 28.7' do
 4" Maple N88W 24.4' do
 18" R.Pine N45W 18.6' do
 Bearings are magnetic.
 Drill rod plat monument East 152.2'
 Drill rod plat monument West 513.61'

(C-N-SE 1/64) 1"IDx32" I.P. w/ 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" R.Pine N16E 20.0' mrkd "1/64S BT"
 18" R.Pine S78E 15.4' do
 9" Oak in clump S09W 34.0' do
 5" W.Pine N42W 12.75' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 05/27/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

