

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>6</u> T <u>42N</u> R <u>31W</u>	<u>C-N-SW 1/64</u>
	S <u>6</u> T <u>42N</u> R <u>31W</u>	<u>14</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 04/07/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C-N-SW 1/64, Sec. 6) 1/64 corner between 1/16 corner #8 and 1/16 corner #11, being the SW corner of the N1/2 of the NE1/4 of the SW1/4 of Section 6. Not established in the original survey.

(14-Sec. 6) South 1/16 corner between Sections 5 and 6. Not established in the original survey. Established in 1959 as the NE corner of the recorded Plat of Martinson-Shemky Subdivision, Liber 3 of Plats, Page 25, Iron County Records. The corner is described on the plat as being monumented with an iron bar encased in a concrete cylinder.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-N-SW 1/64, Sec. 6) Established the corner midway and on a straight line between 1/16 corners #8 and #11, 664.34' north and south.

(14-Sec. 6) Found a 1" drill rod set firm, in good condition, projecting about 1 ft. above ground, and whose location conforms to the record described on the plat of Martinson-Shemky Subdivision. Accepted same as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-N-SW 1/64) 1"IDx32" I.P. with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:	(14) Fd. 1" drill rod. S04W 66.0' Fd. 1.25" dia. iron pin S63E 16.3' Fd. 1.5" O.D. iron pipe Set measuring nail with MDNR tag in the side of:
6" J.Pine S84E 34.3' mrkd "1/64S BT"	20" R.Pine N43E 16.4' mrkd "1/16S BT"
6" J.Pine S66E 30.6' do	9" Maple S67E 35.3' do
4" Cherry S44W 3.7' do	9" Maple S64W 17.7' do
8" J.Pine N26W 11.6' do	4" Maple N26W 40.1' do
Bearings are magnetic.	Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 05/27/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities

16215
16216