

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>42</u> N. <u>X</u> , R. <u>31</u> X. <u>W.</u>	<u>K 11 & K 12</u>
2. PROPERTY CONTROLLING IN SECTION <u>36</u>	, T. <u>42</u> N. <u>X</u> , R. <u>31</u> X. <u>W.</u>	<u>3</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. <u>W.</u>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey or _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner K11: Cedar post (Found.)
 Cedar 12 N45W 3 (")
 Cedar 10 S37E 51 (")

Corner K12: Sugar post (Not found.)
 Sugar 10 N30W 5 (" " No subsequent accessories found.)
 Sugar 14 S31E 26 " " " " " "

Corner 3: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner K11: Remonumented and re-witnessed on 5/10/73. Original artifacts found by probing in water-covered beaver marsh. All in much deteriorated condition but recognizable by axe marks and relative positions and sizes. This corner difficult to recover, probably not seen since late 19th century. Others had adopted places N49 1/2°W .723 ch. and .765 ch. and N3°W .418 ch. for the corner, as evidenced by found pipes and posts.

Corner K12: Re-established 5/17/74 on line between Sec. Cor. 40.249 ch. to N and to S. Found an iron pipe S67°E 43.2 ft., possibly set at the direction of H. Larson, Jr., but apparently not original nor properly re-established.

Corner 3: Established 5/20/74 on line between Sec. Cor. 20.125 ch. N and 1/4 cor. 20.125 ch. S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner K11: 1" I.D. x 36" iron pipe with 4" aluminum cap.
 W. Pine 21 S 50°W (mag.) 379.5 ft. "S35, NBT"
 Tamarack 17 S 70°E (mag.) 283.5 ft. "S36, NBT"

Corner K12: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
 Red Maple 6 S67°W (mag.) 38.6 ft. "1/4S, NBT"
 Y. Birch 9 S 9°W (mag.) 29.2 ft. "1/4S, NBT"

Corner 3: 1" I.D. x 48" iron pipe with 4" brass cap.
 No witnesses, as corner falls in open grass marsh.
 Set cedar guard post.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE July 21, 1974

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

