

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>42</u> N. <u>X.</u> R. <u>31</u> X. <u>W.</u>	<u>K9; K10; L9</u>
2. PROPERTY CONTROLL-25 ING IN SECTION_____	T. <u>42</u> N. <u>X.</u> R. <u>31</u> X. <u>W.</u>	<u>1</u>
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. _____ R. _____ X. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corners K9, K10, and L9: Found no evidence of original posts or their accessories. At K9, found two 2"x2" squared posts N13°W 11.4 ft., and at K10 found a 3"x3"x4½" squared hardwood post rotted off at ground level, all believed to have been placed to mark the approximate corner locations. Nothing found at L9.

Corner 1: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner K9: Re-established 6/12/73 by double proportionate measurement from corners 80.220 ch. N, 80.220 ch. S, 79.937 ch. E, and 79.734 ch. W.
Corner K10: Re-established 6/12/73 on line between Sec. Corners 40.110 ch. to N and to S.
Corner L9: Re-established 8/16/73 on line between Sec. Corners 39.968 ch. to E and to W.
Corner 1: Established 6/14/74 on line between 1/4 cor. 19.984 ch. E and Sec. Cor. 19.984 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for Corners K9 & K10: 1" I.D. x 36" iron pipes with 4" aluminum caps.

Witnesses for Corner K 9: Sugar Maple 5 N 3°W (mag.) 25.5 ft. "S23, NBT"
 Sugar Maple 5 N69°E (mag.) 15.8 ft. "S24, NBT"
 Sugar Maple 6 S28½°E (mag.) 24.7 ft. "S25, NBT"
Witnesses for Corner K10: Sugar Maple 6 S67°W (mag.) 35.2 ft. "1/4S, NBT"
 Sugar Maple 6 N81°E (mag.) 26.8 ft. "1/4S, NBT"

Corner L9: 1" I.D. x 34" iron pipe with 3½" aluminum cap.
 Sugar Maple 6 N71°E (mag.) 10.4 ft. "1/4S, NBT"
 Red Maple 6 N58½°W(mag.) 8.4 ft. "1/4S, NBT"

Corner 1: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 Cedar stump 14 S26°W (mag.) 12.2 ft. "BT"
 Cedar stump 14 N68°W (mag.) 11.3 ft. "BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE July 31, 1974

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

