

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>42</u> N. <u>X</u> , R. <u>31</u> E. <u>W</u> .	<u>K5 & L5</u>
2. PROPERTY CONTROLLING IN SECTION <u>13</u>	, T. <u>42</u> N. <u>X</u> , R. <u>31</u> E. <u>W</u> .	<u>1</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. <u>W</u> .	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram ~ over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner K5:** Sugar post) Not found. Found a 4"x4"x5' squared cedar
 Hemlock 36 N60W 38) post N40W 22.0 ft. for an approx. cor.
 Y. Birch 14 S35E 37) No subsequent accessories.
- Corner L5:** Sugar post) Not found. Found a 4"x4"x6' squared cedar
 Spruce 10 N58W 36) post N65W 18.6 ft. for an approx. cor. No
 Y. Birch 8 S37E 13) subsequent accessories.
- Corner 1:** Not established in original survey. Found a 3"x3"x6' squared cedar post
 N47W 25.7 ft. for an approx. cor.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner K5:** Re-established 4/22/74 by double proportionate measurement from corners
 2 miles N, 1 mile S, 1 mile E, and 2 miles W. on 5/16/74.
- Corner L5:** Re-established on line between Sec, Corners 40.160 ch. to E and to W, /
- Corner 1:** Established 5/21/74 on line between Sec. Cor. 20.085 ch. W and 1/4 cor.
 20.085 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Monuments for all three corners:** 1" I.D. x 36" iron pipe with 3½" aluminum cap.
- Witnesses for Corner K5:** Red Maple 6 N83°E (mag.) 33.4 ft. "S12, NBT"
 Sugar Maple 7 N69°W (mag.) 32.1 ft. "S11, NBT"
- Witnesses for Corner L5:** B. Spruce 6 N61°E (mag.) 72.5 ft. "1/4S, NBT"
 B. Spruce 6 N66½°W (mag.) 49.1 ft. "1/4S, NBT"
- Witnesses for Corner 1:** B. Spruce 6 S86°W (mag.) 33.4 ft. "1/16S, BT"
 B. Spruce 4 N71°E (mag.) 9.4 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 27, 1974
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

