

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY_____	T. <u>42</u> N. <u>31</u> E. <u>X</u> S. R. W.	<u>J7</u>	REGISTER OF DEEDS STAMP AND FILING NUMBER
2. PROPERTY CONTROLLING IN SECTION <u>23</u>	T. <u>42</u> N. <u>31</u> E. <u>X</u> S. R. W.	<u>1 & 2</u>	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. R. W.	_____	
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 13, 1974 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner J7: Hemlock post (Not found. L.E.S. control post S7°W 18.4 ft.
Y. Birch 20 N80E 30 (Not found. No subsequent accessories found)
Sugar 8 S40W 12 (Not found. No subsequent accessories found)
- Corner 1: Not established in original survey. Found a steel fence post S15°W 4.0 ft., set at the site of two badly rotted wood posts; but whoever placed seems only to have done it by an educated guess.
- Corner 2: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner J7: Re-established on line between Sec. Corners 39.98 ch. to E and to W. L.E.S. post is propped up with a steel fence post similar to the one found at Corner 1.
- Corner 1: Established on line between Sec. Cor. 19.99 ch. W and 1/4 cor. 19.99 ch. E.
- Corner 2: Established on line between Sec. Cor. 19.99 ch. E and 1/4 cor. 19.99 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Monuments for all three corners: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
- Witnesses for Corner J7: Twin Red Maple 6 N63°W (mag.) 3.8 ft. "1/4S, NBT"
Sugar Maple 6 S27°W (mag.) 30.7 ft. "1/4S, NBT"
- Witnesses for Corner 1: Sugar Maple 12 S53°W (mag.) 5.6 ft. "1/16S, BT"
Red Maple 8 S79°E (mag.) 25.3 ft. "1/16S, BT"
- Witnesses for Corner 2: B. Ash 5 N59°W (mag.) 35.8 ft. "1/16S, BT"
Elm 18 N29°E (mag.) 10.8 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 28, 1974
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

