

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. <u>31</u> W. <u>X</u> S. R. <u>31</u> W.	<u>K6</u>
2. PROPERTY CONTROLLING IN SECTION <u>13</u>	T. <u>42</u> N. <u>31</u> W. <u>X</u> S. R. <u>31</u> W.	<u>3 & 10</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. S. R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on April 22, 1974 ~~xxxx~~, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner K6:** Cedar post (Not found. No subsequent monuments found.)
 Sugar 16 N57E 33 (Not found. No subsequent accessories found.)
 Cedar 12 S 8W 33 (Not found. No subsequent accessories found.)
- Corner 3:** Not established in original survey. Found a 3"x3"x4" squared cedar post N59°W 33.1 ft., placed for an approximate corner.
- Corner 10:** Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner K6:** Re-established on line between Sec. Corners 40.100 ch. to N and to S.
- Corner 3:** Established on line between Sec. Cor. 20.050 ch. N and 1/4 cor. 20.050 ch. S.
- Corner 10:** Established on line between Sec. Cor. 20.050 ch. S and 1/4 cor. 20.050 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner K6:** 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 Red Maple 5 N32°E (mag.) 14.7 ft. "1/4S, NBT"
 Red Maple 11 S61°E (mag.) 51.6 ft. "1/4S, NBT"
- Corner 3:** 1" I.D. x 40" iron pipe with 3½" aluminum cap.
 Sugar Maple 24 N49°E (mag.) 39.0 ft. "1/16S, BT"
 No other trees near. Distance is horizontal.
- Corner 10:** 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 Sugar Maple 5 N70°E (mag.) 9.8 ft. "1/16S, BT"
 Sugar Maple 6 S42°W (mag.) 26.6 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 28, 1974

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

