

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. XX R. <u>31</u> XX W.	J 5
2. PROPERTY CONTROLLING IN SECTION <u>14</u>	, T. <u>42</u> N. XX R. <u>31</u> XX W.	1 & 2
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ R. _____ E. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner J5: Sugar post (Not found. No subsequent monuments found.)
 Sugar 8 N44W 14 (" " " " accessories ")
 Lynn 18 S30E 31 (" " " " " ")

Corner 1: Not established in original survey. Found a 3"x3"x5' squared cedar post N21°W 15.5 ft. for an approx. corner.

Corner 2: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner J5: Re-established 5/23/74 on line between Sec. Corners 39.790 ch. to E and to W. Found a 2" x 2" squared picket N15°W 28.6 ft. for an approx. corner.

Corner 1: Established 5/23/74 on line between Sec. Cor. 19.895 ch. W and 1/4 cor. 19.895 ch. E.

Corner 2: Established 5/17/74 on line between Sec. Cor. 19.895 ch. E and 1/4 cor. 19.895 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners 1" I.D. x 36" iron pipe with 3½" aluminum cap.

Witnesses for Corner J5: W. Spruce 4 N35°W (mag.) 46.6 ft. "1/4S, NBT"

W. Spruce 5 S80°W (mag.) 57.0 ft. "1/4S, NBT"

Witnesses for Corner 1: Sugar Maple 8 N74°W (mag.) 19.4 ft. "1/16S, BT"

Sugar Maple 8 S35½°E (mag.) 15.9 ft. "1/16S, BT"

Witnesses for Corner 2: Red Maple 5 N88°E (mag.) 12.9 ft. "1/16S, BT"

Red Maple 7 N64°W (mag.) 35.4 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE August 20, 1974

MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

