

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>42</u> <sup>N.</sup> <del>XX</del> R. <u>31</u> <sup>XX</sup> <del>W.</del>	15
2. PROPERTY CONTROL-15 ING IN SECTION_____	T. <u>42</u> <sup>N.</sup> <del>XX</del> R. <u>31</u> <sup>XX</sup> <del>W.</del>	2 & 7
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ <sup>N.</sup> <del>XX</del> <sup>E.</sup> <del>W.</del> R. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

1 Row

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner 15: Maple post (Not found. Wood post N1°E 6.7 ft. for app. cor.)  
 Hemlock 18 N22E 32 (" " No subsequent accessories found.)  
 Y. Birch 8 S29W 36 (" " " " " " " " )

Corners 2 & 7: Not established in original survey nor subsequently, apparently.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner 15: Re-established 5/23/74 by double proportionate measurement from corners 1/2 mile S, 2 miles N, 1 mile W, and 2 miles E.  
 Corner 2: Established 5/29/74 on line between Sec. Cor. 20.020 ch. E and 1/4 cor. 20.020 ch. W.  
 Corner 7: Established 5/23/74 on line between Sec. Cor. 20.140 ch. N and 1/4 cor. 20.140 ch. S.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Monuments for all three corners: 1" I.D. x 36" iron pipe with 3½" aluminum cap.  
 Witnesses for Corner 15: W. Pine 15 N33°W (mag.) 30.4 ft. "S10, NBT"  
 W. Pine 14 S49°W (mag.) 20.4 ft. "S15, NBT"  
 Witnesses for Corner 2: W. Pine 9 S47°E (mag.) 27.5 ft. "1/16S, BT"  
 W. Pine 9 S34°W (mag.) 49.0 ft. "1/16S, BT"  
 Witnesses for Corner 7: Sugar Maple 7 N37°W (mag.) 21.8 ft. "1/16S, BT"  
 Sugar Maple 10 S52°W (mag.) 33.2 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE November 26, 1974  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

