

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY_____	T. <u>42</u> N. <u>31</u> R. <u>31</u> <u>XX</u> W.	1 2	
2. PROPERTY CONTROLLING IN SECTION <u>2</u>	T. <u>42</u> N. <u>31</u> R. <u>31</u> <u>XX</u> W.	3 & 10b	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on June 3, 1974 19___, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19___, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner I2: Sugar post (Not found. No subsequent monuments found.)
 W. Pine 24 N24W 30 (" " " " accessories found.)
 " 30 S44E 35 (" " " " " ")

Corner 3 & 10b: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner I2: Re-established proportionately on line between Sec. Cor. 40.274 ch. S and Sec. Cor. 39.599 ch. N.
 Corner 3: Established proportionately on line between 1/4 cor. 20.137 ch. S and Sec. Cor. 19.462 ch. N.
 Corner 10b: Established on N. Shore of Erickson Lake on true section line between Sec. 2 & 3, 16.104 ch. S of 1/4 cor. bet. 2 & 3 and 24.169 ch. N of Sec. Cor. 2, 3, 10, & 11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for all three corners: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 Witnesses for Corner I2: Aspen 11 S64°E (mag.) 13.0 ft. "1/4S, NBT"
 Aspen 10 N17°E (mag.) 34.8 ft. "1/4S, NBT"
 Witnesses for Corner 3: Red Pine stump 16 N43°E (mag.) 11.1 ft. "1/16S, BT"
 W. Pine stump 16 S72°E (mag.) 9.5 ft. "1/16S, BT"
 Witnesses for Corner 10b: Tamarack 10 N10°E (mag.) 45.4 ft. "M.C., BT"
 Tamarack 8 N65°W (mag.) 54.2 ft. "M.C., BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE November 26, 1974

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

