

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> ^{N.} XX , R. <u>31</u> ^{SEC} W.	<u>G 11 & I 11</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____, S., R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, S., R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner G11: Cedar post (Not found. Found a 1" x 52" solid round iron bar in place.)
 - Y. Birch 12 N58E 21 (Not found)
 - Y. Birch 12 S54W 24 " "
 - Corner I11: Cedar post (Not found. Found a 1/2" x 48" re-inforcing rod N12°E 49.7 ft.)
 - Y. Birch 18 N68W 41 (Not found)
 - Y. Birch 18 S48E 30 " "

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G11: WMPC records indicate the found iron bar was placed from an original BT, no evidence of which could now be recognized. Distance East to county road centerline 80.32 ch. E, reputed to pass through the sec. cor., checks closely with original record distance. Placed and witnessed a new monument on 5/3/73, as shown below.

Corner I11: Re-established 5/4/73 by proportionate measurement in N & S direction, and 80.32 ch. E of reputed original sec. cor. to W. Corner thus falls almost exactly on observed construction centerline of N & S county road, which appears to have been intended to be placed on the section line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Monuments for both corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses for Corner G11: Red Maple 7 S81°W (mag.) 18.4 ft. "S33, NBT"
 Sugar Maple 5 N16°W (mag.) 36.4 ft. "S28, NBT"
 Sugar Maple 6 N82½°W (mag.) 26.0 ft. "S27, NBT"

Witnesses for Corner I11: Red Maple 7 N29°W (mag.) 66.3 ft. "S27, NBT"
 W. Birch 10 S39°E (mag.) 27.8 ft. "S35, NBT"
 W. Pine 10 N19½°E (mag.) 158.5 ft. "S26, NBT"

Note: Monument at I11 is buried with top about 1 foot below ground level.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE July 31, 1974
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

