

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|--|---|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>42</u> ^{N.} xx , R. <u>31</u> ^{E.} W. | <u>J 11</u> |
| 2. PROPERTY CONTROLLING IN SECTION <u>35</u> | , T. <u>42</u> ^{N.} xx , R. <u>31</u> ^{E.} W. | <u>1 & 2</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | , T. _____ ^{N.} S. , R. _____ ^{E.} W. | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner J11: Sugar post (Not found. No subsequent monuments found.)
 Hemlock 12 N44E 40 (" " " " accessories ")
 W. Pine 18 N11W 23 (" " " " " ")

Corner 1 & 2: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner J11: Re-established 6/12/73 on line between Sec. Cor. 39.863 ch. to E and to W. Found an 8" aspen blazed on 4 sides for an approx. corner, S18°E 13.5 ft.
Corner 1: Established 5/20/74 on line between Sec. Cor. 19.931 ch. W and 1/4 cor. 19.931 ch. E. Foresters' approx. cor. found S50°E 20.7 ft.
Corner 2: Established 5/20/74 on line between Sec. Cor. 19.931 ch. E and 1/4 cor. 19.931 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner J11: 1" I.D. x 36" iron pipe with 4" aluminum cap.
 Red Maple 5 N48°E (mag.) 27.7 ft. "1/4S, NBT"
 Red Maple 8 N18°W (mag.) 57.4 ft. "1/4S, NBT"
Corner 1: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
 Sugar Maple 5 N49°W (mag.) 18.6 ft. "1/16S, BT"
 Red Maple 6 S46 1/2°W (mag.) 26.5 ft. "1/16S, BT"
Corner 2: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
 B. Spruce 6 S 5°E (mag.) 24.4 ft. "1/16S, BT"
 B. Spruce 5 N26 1/2°W (mag.) 36.9 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE July 31, 1974

MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger
 Michigan Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 13581