

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|---|--|----------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>42</u> N. <u>XX</u> , R. <u>31</u> <u>KX</u> V. | <u>K13 & L13</u> |
| 2. PROPERTY CONTROLL- ING IN SECTION <u>36</u> | T. <u>42</u> N. <u>XX</u> , R. <u>31</u> <u>KX</u> V. | <u>15</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. _____, R. _____ E. W. | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner K13:** Hemlock post
Maple 12 N15 1/2 E 55 - Y. Birch 12 S23 E 43 - Y. Birch 12 N37 W 13 - Y. Birch 10 S41 W 33
Original post or its accessories not found. Found a 1" I.D. x 27" iron pipe buried in the approximate construction centerlines of N-S and E-W county roads, set by unknown persons. This monument had been witnessed with a 2" pipe 33.08 ft. to S.
- Corner L13:** Hemlock post
Y. Birch 10 N40 E 18 Hemlock 12 N15 W 29
Original post or its accessories not found. Found an L.E.S. post, plainly labeled "APP", N88°E .265 ch. from corner, at the base of which a 3/4" round iron bar had been placed to perpetuate the post position.
- Corner 15:** Not established in original survey. Found a 1" I.D. x 42" iron pipe S78 1/2°W .080 ch. purporting to be the corner.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner K13:** Accepted the found pipe as the corner by common report. Although it is nearly on the true line between Sec. Corners 2 miles W and 1 mile E, it is not proportional to the original distances between them; in the absence of physical or record evidence, it is not possible to say this is the original corner position. Corner re-monumented on 4/11/73.
- Corner L13:** DNR records indicate that L.E.S. posts are but control points for the land economic survey of the 1930's, therefore cannot be accepted as the true corners unless supported by other evidence. Therefore, on 5/3/73, the corner was re-established on line between section corners 40.160 ch. to E and to W.
- Corner 15:** The found monument appears to have been set at the record distance E of a monument at Sec. Cor. 1, 2, 35, & 36. Therefore, on 5/3/73 the corner was re-established on line between this sec. cor. 20.080 ch. W and the 1/4 corner 20.080 ch. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner K13:** 1" I.D. x 24" iron pipe with 4" aluminum cap, buried in road.
Red Maple 6 S40°W (mag.) 21.5 ft. "NBT"
White Pine 8 N49 1/2°W (mag.) 66.9 ft. "NBT"
- Corner L13:** 1" I.D. x 36" iron pipe with 4" aluminum cap
Red Maple 6 S81 1/2°W (mag.) 20.0 ft. "1/4S, NBT"
White Pine 8 N14 1/2°W (mag.) 24.4 ft. "1/4S, NBT"
- Corner 15:** 1" I.D. x 36" iron pipe with 4" aluminum cap.
Balm-of-Gilead 6 N35°E (mag.) 21.8 ft. "1/16S, BT"
Balsam 6 S88°E (mag.) 8.7 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 27, 1974

Michigan Registered Land Surveyor
Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

