

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>42</u> N. <del>33</del> R. <u>31</u> <del>XX</del> W.	<u>112</u>
2. PROPERTY CONTROLLING IN SECTION <u>35</u>	, T. <u>42</u> N. <del>33</del> R. <u>31</u> <del>XX</del> W.	<u>3 &amp; 10</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 9 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner 112: Hemlock post (not found)**  
 Hemlock 16 N78W 18 " "  
 Sugar 14 S22E 17 " "

No subsequent monuments found. Found a 13" aspen with grown over 4 sided blazes S82°W 8.7 ft. and a similarly marked 8" aspen S87°E 72 ft., for approximate corners.

**Corner 3:** Not established in original survey nor subsequently, apparently.  
**Corner 10:** Not established in original survey. Found a 12" hemlock blazed on 4 sides N77°E 14.6 ft., for an approximate corner.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner 112:** Re-established, by transit and tape traverse, on line between section corners 40.067 ch. to N and to S. Corner is on south edge of a power line clearing.  
**Corner 3:** Established, by transit and tape traverse, on line between section corner 20.034 ch. N and 1/4 corner 20.034 ch. S.  
**Corner 10:** Established, by transit and tape traverse, on line between section corner 20.034 ch. S and 1/4 corner 20.034 ch. N.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for all three corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.  
**Witnesses for Corner 112:** Sugar Maple 6 S13°W (mag.) 9.7 ft. "1/4S, NBT"  
 Red Maple 6 S64°E (mag.) 16.3 ft. "1/4S, NBT"  
**Witnesses for Corner 3:** Red Maple clump N24°E (mag.) 42.2 ft. "BT"  
 White Spruce 8 S20°E (mag.) 65.4 ft. "BT"  
 Distances are horizontal.  
**Witnesses for Corner 10:** Sugar Maple 8 S50°W (mag.) 16.0 ft. "1/16S, BT"  
 Hemlock 10 N24°W (mag.) 33.2 ft., "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE March 18, 1974  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**  
 Michigan Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 13581