

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> ^{N.} XX , R. <u>31</u> ^{XX} W.	<u>I13 & J13</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____, S., R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, S., R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on April 30 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner I13: Sugar post

Y. Birch 16 N36E 34 Y. Birch 20 S44E 47
Y. Birch 10 N52W 39 Y. Birch 10 S20W 4

Original post or its accessories not found. Found an L.E.S. control post S82°W 21.4 ft. from corner.

Corner J13: Ironwood post

Sugar 16 N 8½E 30
Sugar 10 N12½W 23

Original post or its accessories not found. Found a 5" sugar maple with 4-sided blaze scars S5°W 21.5 ft. from corner.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner I13: Re-established, by transit and tape traverse, on line between existing monuments found at Section Corners 79.962 ch. to E and to W. Corner falls nearly at intersection of centerline of N & S county road and S. edge of county road to E on S. side of Sec. 35.

Corner J13: Re-established, by transit and tape traverse, on line between Section Corners 39.981 ch. to E and to W. Corner falls in E & W county road, a little south of the construction centerline.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for both corners: 1" I.D. x 24" iron pipe with 4" aluminum cap.

Witnesses for Corner I13: Sugar Maple 12 N65½°W (mag.) 27.9 ft. "NBT"
Basswood 6 S53°W (mag.) 37.8 ft. "NBT"
W. Spruce 14 N13½°E (mag.) 86.9 ft. "NBT"

Monument buried in road.

Witnesses for Corner J13: Sugar Maple 9 S3°E (mag.) 20.7 ft. "NBT"
Sugar Maple 12 S55°W (mag.) 23.0 ft. "NBT"

Monument buried in road.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE February 27, 1974

MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

