

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 42N R 31-32W

DESCRIPTION OF CORNER 1/4 corner between Sections 1 and 6

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 2, 1972

WITNESSES TO CORNER..... J. Pine 5 S53°E (mag.) 15.9 ft. "1/4S, NBT"



J. Pine 4 N82½°W (mag.) 5.4 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established by proportionate measurement on line between
section corners 40.162 ch. to S and 39.961 ch. to N.

Variation 1°05' East at this corner.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

June 26, 1972