

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Iron Co.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. R. 31 W.	A5, A7, B5
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-16, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner A5: Original monument and accessories not found. Found 2½" I.D. I.P. set by Murry Ates in 1953.

Corner A7: Original monument and accessories not found. Found 2½" I.D. I.P. set by Murry Ates in 1953.

Corner B5: Found ¾" I.D. by unknown length I.P. and pine stump with notch that matches with original BT.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

Corner A5: Restored at Iron Pipe.

Corner A7: Restored at Iron Pipe.

Corner B5: Restored at Iron Pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Corner A5: 2½" I.D. by unknown length I.P.
 12" Jack Pine S64W 2.5 ft. S13,NBT
 12" Red Pine N60W 11.4 ft. S12,NBT
 4" Jack Pine N18E 6.9 ft. S7,NBT

Corner B5: ¾" I.D. by unknown length I.P.
 4" Red Pine N60W 10.9 ft. S5,NBT
 10" Jack Pine S47W 3.6 ft. S5,NBT
 4" Jack Pine S12E 29.2 ft. S5,NBT
 Pine stump with old notch S04W 15.4 ft.

Corner A7: 2½" I.D. by unknown length I.P.
 10" Cedar N42E 23.5 ft. S18, NBT
 8" Balsam S10E 18.5 ft. S19, NBT
 12" Spruce N56W 31.0 ft. S13, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 8-29-85
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

Keith L. Sackett
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006