

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Iron Co.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. R. 31 W.	A6
2. PROPERTY CONTROLLING IN SECTION	18 T. 42 N. R. 31 W.	3, 10
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. S. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-16, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner A6: Original monument and accessories not found.
 Corner 3: Not set on original survey nor subsequently apparently.
 Corner 10: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner.

- Corner A6: Restored midway and on line between section corners north and south.
 Corner 3: Established midway and on line between section corner north and $\frac{1}{4}$ corner south.
 Corner 10: Established midway and on line between $\frac{1}{4}$ corner north and section corner south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

- Corner A6: Set 1" I.D. by 32" I.P. w/4"/AC
 7" Jack Pine S16W 27.0 ft. $\frac{1}{4}$ S, NBT
 10" Jack Pine N80W 20.7 ft. $\frac{1}{4}$ S, NBT
 8" Jack Pine N26E 6.4 ft. $\frac{1}{4}$ S, NBT
- Corner 10: Set 1" I.D. by 32" I.P. w/4"/AC
 6" Cedar S76E 5.9 ft. 1/16S, BT
 7" Cedar N38W 7.8 ft. 1/16S, BT
- Corner 3: Set 1" I.D. by 32" I.P. w/4"/AC
 5" Jack Pine S62W 29.3 ft. 1/16S, BT
 8" Jack Pine N16E 48.3 ft. 1/16S, BT
 6" Jack Pine S82E 40.2 ft. 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (BEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 8-29-85
 MICHIGAN REGISTERED LAND SURVEYOR (BEAL)

Keith L. Sackett
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006