

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
T Iron

	County	Located In	Corner Code #
1	Public Land Survey	T 42N R 31W	J9
		T R	I8
		T R	J10
2	Property Controlling in Section	S 26 T R	12
		S T R	
3	Miscellaneous Property in Sec.	S T R	
		S T R	

Register of Deeds Stamp & File Number

4 Lot No. , Recorded Plat
5 Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	15	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, **Keith Sackett**, in a field survey on **April 24**, 19 **90**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A Description of original monument and accessories and/or subsequent restoration:

J9	I8	J10	12
Found 3/4" ID pipe 1.6' out of ground.	Found Wisconsin-Michigan Power Company monument.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner

J9	I8	J10	12
Restored at 3/4" ID pipe.	Restored at WI-MI Power Co. monument.	Established at intersection of 1/4 lines.	Established midway and on line.


C Description of monument for corner and accessories established to perpetuate locating the position of the corner.

J9	I8	J10	12
3/4" ID iron pipe 1.6' out of ground.	WI-MI Power Co. monument.	Set 8-29-90 1" ID x 32" iron pipe w/4" aluminum cap.	Set 1" ID x 32" iron pipe w/4" aluminum cap.
6" basswood S10E 16.0' 1/4s, BT	8" maple N10E 7.9' 1/4s, NBT	7" sugar S73E 14.0' 1/4s, BT	6" sugar N66E 9.7' 1/16s, BT
6" sugar N75W 17.4' 1/4s, BT	12" yellow birch S65W 1.4' 1/4s, NBT	4" sugar S15W 13.3' 1/4s, BT	8" maple N35W 17.9' 1/16s, BT
5" sugar N46E 14.2' 1/4s, NBT	10" sugar S24E 19.3' 1/4s, NBT	10" sugar N48E 19.0' 1/4s, BT	3" sugar S70W 5.5' 1/16s, BT

Signed by Keith Sackett Date _____

Surveyor's Michigan License No

19006



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1979
REVISED JAN. 1983