

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Iron

(County)	Located In	Corner Code #
1 Public Land Survey	T 42N R 31W	
	T R	
	T R	
	T R	
2 Property Controlling in Section	S 26 T R	10
	S T R	8
	S T R	4
3 Miscellaneous Property in Sec	S T R	3
	S T R	

Register of Deeds Stamp & File Number

4 Lot No _____ Recorded Plat _____
5 Private Claims _____

I, Keith Sackett in a field survey on September 4, 1990 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4													
5													
6	14	15	16	17	18	19	20	21	22	23	24	25	26
7													
8	27	28	29	30	31	32	33	34	35	36	37	38	39
9													
10	40	41	42	43	44	45	46	47	48	49	50	51	52
11													
12	53	54	55	56	57	58	59	60	61	62	63	64	65
13													

A Description of original monument and accessories and/or subsequent restoration:

10 Found Art Enger witness tree.	8 Not set on original survey nor subsequently, apparently.	4 Not set on original survey nor subsequently, apparently.	3 Found Art Enger corner with BTs cut.
-------------------------------------	---	---	---

B Description of corner evidence found and/or method applied in restoring or reestablishing corner

10 Replaced from witness tree.	8 Established midway and on line.	4 Established during section subdivision.	3 Replaced witnesses.
-----------------------------------	--------------------------------------	--	--------------------------

C Description of monument for corner and accessories established to perpetuate locating the position of the corner.

10 Set 1" ID x 36" iron pipe w/4" aluminum cap.	8 Set 1" ID x 36" iron pipe w/4" aluminum cap.	4 Set 1" ID x 32" iron pipe w/4" aluminum cap.	3 Old BTs cut.
7" maple S45W 49.4' 1/16s, BT	8" sugar S59W 5.7' 1/16s, BT	10" maple N20E 9.6' 1/16s, BT	10" v. pine S64W 17.6' 1/16s, BT
7" maple N55E 29.5' 1/16s, BT	10" maple N54W 12.8' 1/16s, BT	4" sugar S24W 10.7' 1/16s, BT	12" v. pine N55W 38.2' 1/16s, BT
20" r. pine N25W 77.2' 1/16s, BT	8" sugar S48E 18.1" 1/16s, BT	6" sugar N67W 44.4' 1/16s, BT	7" maple North 17.8' 1/16s, BT
	4" ironwood N73W 2.2' squared	3" sugar S17W 4.0' squared	

Signed by

Keith Sackett

Date

September 11, 1990

Surveyor's Michigan License No

19006

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28 1971
REVISED MAY 14 1975
REVISED JAN 1983

