

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 31W	E12
	T 42N R 31W	F13
	T R	
2. Property Controlling In Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property In Sec.	S T R	
	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Stephen J. Szyszkoski, in a field survey on September 26, 1994, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(E12) Quarter corner common to Sections 32-33. Corner established in 1849 by John Burt as follows: "Set Hemlock qr 8 post. Hemlock 12 N48E 18, do 14 S34W 16". Corner remonumented in the 1940's by Wisconsin Michigan Power Company as follows: "Set concrete marker, Checks to river 1 mile north and S. 1/2 mile. 5" Pop. S83W 9.9", 4" Pop. N48E 2.5", 3" Pop. S35E 5.8". Found no subsequent record.  
(F13) Quarter corner common to Section 33 T42N-R31W and Section 4 T41N-R31W. Corner established in 1848 by Wm A. Burt as follows: "Set Hemlock post qr Sec. cor. Hem. 18 N58E 25, W. Pine 40 N10W 23". Corner remonumented in the 1940's by Wisconsin Michigan Power Company as follows: "Found old Sq. tree. Set pipe marker. 24" Y. Birch S23E 48.5", 8" Pop. N45E 23.4". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E12) Found the WMPCO monument - a truncated right-rectangular concrete pyramid, of unknown depth, containing ferrous material, with a 3 1/2" dia. stamped brass tablet set in the top, in good condition. None of the WMPCO NBTs were recovered. Distance north to WMPCO monument at the section corner was determined to be 39.844 ch.(40.00 ch. original record). Made no further attempt to verify the WMPCO position. Marked 4 new witnesses as described below.  
(F13) Recovered the WMPCO monument at record bearing and distance from the remaining NBT, the Y. Birch, now stump remains. The monument is in good condition. Made no further attempt to verify the WMPCO position. Left the monument in place and marked 4 new bearing trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E12) Found a Concrete monument with 3 1/2" dia. WMPCO tablet. Blazed and scribed the following bearing trees:	(F13) Found a 2" I.D.x unknown length iron pipe capped with a 3 1/2" dia. brass WMPCO cap. Blazed and scribed the following new bearing trees:
12" Maple S25E 21.5' "1/4S NBT"	10" twin Maple N37E 19.7' "1/4S NBT"
10" Maple S21W 13.9' "1/4S NBT"	8" Maple S25W 34.3' "1/4S NBT"
7" Maple N85E 20.3' "1/4S NBT"	10" twin Maple S84W 37.7' "1/4S NBT"
9" Maple N65W 49.8' "1/4S NBT"	8" Maple N26W 25.5' "1/4S NBT"
Bearings are magnetic.	Bearings are magnetic.



Signed by Stephen J. Szyszkoski Date 10-10-94  
Surveyor's Michigan License No. 33986