

(69)

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 42N R 31W	E7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 20 T 42N R 31W	7
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

7 Aug 07 1996  
E7 Aug 13 1996

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
(E7) Corner common to Sections 16-17-20-21. Corner established in 1849 by John Burt. "80.00 Set cedar post corner of Sec. 16, 17, 20, 21. Fir 10 N38W 10, W. Pine 20 S58E 10". Records of Wisconsin Michigan Power Company (now Wisconsin Electric Power Company) in the form of a map titled PROPERTY MARKERS PAINT AND MICHIGAN RIVERS map #G-210-GG dated 4/10/1947 show in regard to this corner: "24" down pine sq. on side toward corner. Set concrete marker. 5" spruce N30W 22.9', 5" W. Pine N54E 20.4', 12" W. Birch S45W 12.2'". (7-Sec. 20) North 1/16 corner between Sections 20-21. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E7) Original post and accessories not recovered. Found a 7" truncated right rectangular pyramid shaped concrete monument with a 3" square brass tablet affixed on the top which is stamped to read: "Wisconsin Michigan Power Company...42-31 16-17-20-21". Recovered the WMPCD witnesses as follows: 20" Spruce N30W 22.9' in good condition, 9" W. Pine, dead with no markings visible, N54E 20.4' to center. The W. Birch was not found. Accepted the monument as the best available evidence of the position of the original corner.  
(7-Sec. 20) Found no evidence of prior monumentation at the corner position. Established the corner on a straight line between 1/4 quarter corner 1310.38' south and section corner 1310.38' north. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MOHR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E7) Found WMPCD concrete monument.  
Blazed and scribed the following new bearing trees:

24" W. Pine S06W 45.1' "S20 NBT"  
10" Cedar S44W 38.4' "S20 NBT"  
16" Red Pine N47W 50.3' "S17 NBT"  
15" Cedar N52E 70.5' "S16 NBT"

Placed a squared maple post adjacent.  
Bearings are magnetic.

(7) Set 1" pipe with MOHR aluminum cap.  
Blazed and scribed the following bearing trees:

3" Maple N04W 38.4' "1/16S BT"  
4" W. Spruce N55E 6.7' "1/16S BT"  
8" Maple S24E 40.1' "1/16S BT"  
9" double Maple S56W 52.7' "1/16S BT"

Placed a 5" squared poplar post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 9-9-96

For the Michigan Department of Natural Resources - Forest Management Division