

73

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron _____	Located in:	Corner Code #
(County)		
1. Public Land Survey	T 42N R 31W	A8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 20 T 42N R 31W	3
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

3 Aug 13 1996
A8 Aug 14 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


A. Description of original monument and accessories and/or subsequent restoration:
(A8) Corner common to Section 19 T42N-R31W and Section 24 T42N-R32W. Corner established in 1846 by William A. Burt: "40.00 Set spruce post qr Section corner. Y. Birch 10 N68E 3, spruce 9 S51W 12". Records of Wisconsin Michigan Power Company (now Wisconsin Electric Power Company) in the form of a map titled PROPERTY MARKERS PAINT AND MICHIGAN RIVERS map 8G-210-GG dated 4-10-1947 state in regard to this corner: 1 orig. BT set concrete marker. 7" Balsam N27W 7.7', 6" Tan S25E 20.4'.
(3-Sec. 20) North 1/16 corner between 19-20. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A8) Recovered a 7" truncated right rectangular pyramid shaped concrete monument with a 3" square brass tablet affixed to it's top which is stamped: "Wisconsin Michigan Power Company 42-31 32, 1/4 cor 24/19". The monument was recovered at record bearing and distance from the 1947 witnesses: The tamarack is now dead and down, and the balsam has been reduced to a mossy mound. Recovered the probable remains of the original spruce BT, now a mossy mound, at record bearing and distance. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.
(3-Sec. 20) Found no evidence of prior monumentation at the corner position. Established the corner on a straight line between 1/4 corner 1317.89' south and section corner 1317.89' north. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A8) Found WMPCO concrete monument.	(3) Set 1" pipe with MDNR alumina cap.
Blazed and scribed the following bearing trees:	Blazed and scribed the following bearing trees:
5" Spruce N85E 39.1' "1/4S NBT"	4" Balsam N15E 9.7' "1/16S BT"
12" Cedar S64E 29.9' "1/4S NBT"	8" Jack Pine S41E 10.2' "1/16S BT"
6" Spruce S52W 30.3' "1/4S NBT"	7" Jack Pine S01W 12.7' "1/16S BT"
16" Cedar N17W to notch, 22.3' do	10" Jack Pine N36W 40.1' "1/16S BT"
Placed a 3" cedar post adjacent.	Placed a 4" squared maple post adjacent.
Bearings are magnetic.	Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 9-9-96

For the Michigan Department of Natural Resources - Forest Management Division