

75

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iran <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>31W</u>	<u>C9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u>20</u> T <u>42N</u> R <u>31W</u>	<u>2</u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

2 Aug 12 1996
C9 Aug 13 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(C9) Corner common to Sections 19-20-29-30. Corner established in 1849 by John Burt. "80.00 Set Cedar post corner of Sections 19,20,29,30. Cedar 14 S66N 22, do 18 N38E 24". Records of Wisconsin Michigan Power Company (now Wisconsin Electric Power Company) in the form of a map titled PROPERTY MARKERS PAINT AND MICHIGAN RIVERS map #G-21-GG dated 4-10-1947, shows in regard to this corner, "Original cedar post and 1 B.T. below 1285' elev. Set concrete marker 594' west of cor 19-20-29-30. 4" Poplar N80E 6.3', 3" Poplar N37E 14.5', 3" Poplar N52W 5.8'".
(2-Sec. 20) East 1/16 corner between Sections 17-20. Corner not established in the original survey. Found no subsequent record.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C9) Original post and accessories now considered lost beneath the surface of Peavy pond. Found a 7" truncated right rectangular pyramid shaped concrete monument with a 3" square brass tablet affixed on top which is stamped to read: "Wisconsin Michigan Power Company 42-31 19-20-29-30 594' east to cor.". None of the WMPCO witnesses were recovered. Accepted the monument as a reference to the original corner and reestablished the corner 594.00' due east (astronomic or true east) from the WMPCO monument. The position for the corner falls in Peavy Pond and was not monumented. The corner position was used to reestablish the 1/4 corner common to Sections 20-29, to verify the position of the 1/4 corner between 19-20, and to subdivide Section 20. Witnesses below are to the reference monument.

(2-Sec. 20). Found no evidence of prior monumentation at the corner position. established the corner on a straight line between 1/4 corner 1319.44' West and Section corner 1319.44' East. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MONR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C9) Found WMPCO concrete reference monument.	(2) Set 1" pipe with MONR aluminum cap.
Blazed and scribed the following bearing trees:	Blazed and scribed the following bearing trees:
8" Maple N45E 21.0' "RM BT"	11" J. Pine S44N 24.4' "1/16S BT"
9" W. Pine N37W 34.9' "RM BT"	12" Twin R. Pine S69E 62.2' "1/16S BT"
9" W. Pine S50W 36.9' "RM BT"	12" J. Pine N37E 130.7' "1/16S BT"
3" Maple N01W 13.6' "RM BT"	4" W. Pine N06W 74.1' "1/16S BT"
Placed a 3" squared maple post adjacent.	Centerline of road is 12' east.
Bearings are magnetic. The water's edge is 6' east, course NSOE.	Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 9-9-96

For the Michigan Department of Natural Resources - Forest Management Division