

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 35 T 42N R 32W	4
	S _____ T _____ R _____	(GCDB 520160)
	S 35 T 42N R 32W	8
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	(GCDB 520140)
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 05/13/14 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(4-Sec. 35) Northwest 1/16 corner, Section 35. Not previously monumented.

(8-Sec. 35) Center West 1/16 corner, Section 35. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(4-Sec. 35) Established the position for the corner at the intersection of straight lines connecting opposite 1/16 corners.

(8-Sec. 35) Established the position for the corner midway and on a straight line between Quarter corner 1318.26' west and the Center of Section 35 1318.26' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(4) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 8" Maple N34°E 26.6' mrkd "1/16S BT"
 4" Balsam S89°E 6.05' do
 4" Balsam S52°W 16.05' do
 4" Balsam N21°W 7.1' do
 Set sq'd cedar post adjacent.
 E= 7900973.507 N= 135653.270

(8) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 8" Balsam N68°E 79.75' mrkd "1/16S BT"
 14" Spruce S21°E 13.45' do
 11" Spruce S52°W 25.95' do
 6" Maple in clump N73°W 33.85' do
 Set sq'd cedar post adjacent.
 E= 7900967.772 N= 135250.705

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)
 Coord. Ref.=NGS PID AA8081: N= 147176.690 m. E= 7895147.466 m.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 06/04/2014



For the Michigan Department of Natural Resources, Forest Resources Division