

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Iron

(County)

Located In:

Corner Code #/

- 1. Public Land Survey Section 8 T 42N R 32W D-5
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

95 JAN 17 AM 8:42
L.C. RECORDS L.C. P. 337

Spilner & Stiles
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____
 One-quarter corner common to Sections 8 and 17,
 T42N, R32W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	31	32	33	34	35	36						
11													
12	31	32	33	34	35	36							
13													

I, John R. Garske, in a field survey on October 18, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by J.B. Seal on September 24, 1849. Set hemlock post from which a 10" hemlock - S46°W, 36 and a 8" hemlock - N50°E, 30 links.

Survey by Michigan Department of Natural Resources surveyor, Arthur O. Enger, RLS 13581, on July 23, 1971. Set 1" I.D. x 36" iron pipe with a 4" aluminum description cap, 6" R. maple - N13°E, 25.4 feet; 22" W. pine - S86°W, 48.5 feet. Corner record form November 27, 1972, supplied by MDNR.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Michigan Department of Natural Resources monument as noted above. Enger's notes state that the corner position was re-established on line between section corners 40.006 chs. to east and west.

I accepted the DNR monument after making distance checks to other monumented corners from information supplied by the MDNR.

County Record Research and field search forms on file with County Representatives offices.


PEER GROUP APPROVED

Iron County Surveyors

COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: AP 12-15-94

Updated Michigan Department of Natural Resources monument to state and county specifications. Established the following bearing trees and reference object: 8" maple - N18°E, 25.66 feet; 8" W. pine - S62°E, 13.47 feet; 8" W. pine - S09°W, 10.89 feet; 5" oak - N84°W, 28.75 feet; 6" steel rail with sign - North - 1.0 foot.



Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 12/12/94