

# SURVEY & REMONUMENTATION

APR 27 1995

## COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Iron  
(County)

Located In:

Corner Code #

1. Public Land Survey	Section 8	T 42N	R 32W	E-3
		T	R	
		T	R	
		T	R	
2. Property Controlling In Section	S	T	R	
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

95 JAN 17 AM 8:42  
L.C. RECORDS L.C. P. 334

*Edwin J. Stiles*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_  
Section corner common to Sections 4, 5, 8 and 9  
T42N, R32W

I, John R. Garske, in a field survey on October 18, 1994  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by J.B. Seal on September 23, 1849. Set Y. pine post from which a 10" spruce  
pine S55°E, 22 links and a 8" Y. pine - N65°W, 15 links.

Survey by Michigan Department of Natural Resources surveyor, Arthur O. Enger, RLS 13581,  
on October 31, 1972. Set 1" I.D. x 36" iron pipe with a 4" aluminum description cap, 8" J. pine -  
S03°E, 4.9 feet; 7" J. pine - N81°E, 13.2 feet; 7" J. pine - N37°E, 8.9 feet.

1976 MDOT R/W plans for US-2 show corner position from highway centerline.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Michigan Department of Natural Resources monument as noted above. Enger's notes state  
that the corner position was re-established by double proportionate measurement from corners 1  
mile north, 2 miles south, 1 mile west and 1 mile east.

County Record Research and field search forms on file with County  
Representatives offices.

PEER GROUP APPROVED

*Iron* *Amy J. Pore*

COUNTY REPRESENTATIVE

*AP. 12-15-94*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Updated Michigan Department of Natural Resources monument to state and county specifications.  
Established the following bearing trees and reference object: 6" R. pine - N01°E, 52.97 feet; 9" J.  
pine - N85°E, 13.71 feet; 8" oak - S23°W, 98.41 feet; 8" oak - West, 133.05 feet; 6' steel rail with  
sign - North, 1.0 foot.

Signed by John R. Garske  
Surveyor's Michigan License No. 28410

Date 12/12/94



FOAM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

LIBER:

6 PAGE 334

Fed. No. E-9