

SURVEY & REMONUMENTATION

APR 27 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Iron
(County)

Located In:	Corner Code #
1. Public Land Survey Section 8 T 42N R 32W	E-4
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
2. Property Controlling S _____ T _____ R _____	_____
In Section S _____ T _____ R _____	_____
3. Miscellaneous S _____ T _____ R _____	_____
Property in Sec. S _____ T _____ R _____	_____

IRON COUNTY MICHIGAN
RECEIVED FOR RECORD

95 JAN 17 AM 8:42
L.C. RECORDS L.6 P.335

Edwin Stebbins
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
One-quarter corner common to Sections 8 and 9, T42N, R32W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	14	15	16	17	18							
7													
8	19	20	21	22	23	24							
9													
10	25	26	27	28	29	30							
11													
12	31	32	33	34	35	36							
13													

I, John R. Garske, in a field survey on October 18, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by J.B. Seal on September 23, 1849. Set Y. pine post from which a 8" Y. pine - S35°W, 22 links and a 8" spruce pine - N35°E, 4 links

Survey by Michigan Department of Natural Resources surveyor, Arthur O. Enger, RLS 13581. Set a 1" I.D. x 36" iron pipe with a 4" aluminum description cap, 7" J. pine - S50°E, 25.3 feet; 7" J. pine - N09°W, 9.4 feet. Corner record form dated November 27, 1972, supplied by MDNR.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Michigan Department of Natural Resources monument as noted above. Enger's notes state that the corner position was re-established on line between section corners 39.977 chs. to the north and to the south.

Information supplied by MDNR's Baraga office showed distances to other monumented corners which I was able to confirm.

PEER GROUP APPROVED
Edwin Stebbins
COUNTY REPRESENTATIVE


County Record Research and field search forms on file with County Representatives offices.

A.P. 12-15-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Updated Michigan Department of Natural Resources monument to state and county specifications. Established the following bearing trees and reference object: 11" J. pine - S71°E, 50.46 feet; 6" R. pine - S02°E, 77.77 feet; 8" R. pine - S83°W, 53.62 feet; 11" J. pine - N09°E, 30.30 feet; 6' steel rail with sign - North - 1.0 foot.

Signed by John R. Garske Date 12/12/94
Surveyor's Michigan License No. 28410



LIBER 6 PAGE 335 Fed. No. G-9