

# SURVEY & REMONUMENTATION

APR 27 1995

## COMMISSION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Iron  
(County)

Located In: Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey Section 8    | T <u>42N</u> R <u>32W</u> | <u>E-5</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

95 JAN 17 AM 8:42  
L.C. RECORDS L.C. P. 336

*Gilbert Seal*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section corner common to Sections 8, 9, 16 and 17,  
T42N, R32W

I, John R. Garske, in a field survey on October 18, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original survey by J.B. Seal on September 24, 1849.

Survey by Michigan Department of Natural Resources surveyor, Arthur O. Enger, RLS 13581. Set a 1" I.D. x 36" iron pipe with a 4" aluminum description cap, 4" aspen - N2°-30'E, 8.9; 3" aspen - N60°W, 15.0 feet; 1 1/2" I.D. iron pipe - N74°-30'E, 33.7 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Michigan Department of Natural Resources monument as noted above. Enger's notes state that the corner position was re-established by single proportionate measurement on line between section corners 1 mile north and 1 mile south.

Accepted MDNR monument after making distance checks to other monumented corners in the area from information supplied by MDNR, Baraga.

County Record Research and field search forms on file with County Representatives offices.

PEER GROUP APPROVED

*IRM Gary L. Poon*

COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: *AP 12-15-94*

Updated Michigan Department of Natural Resources monument to state and county specifications. Established the following bearing trees and reference object: 4" aspen - N52°E, 16.60 feet; 2" iron pipe - N80°E, 33.57 feet; 8" oak - S06°W, 27.88 feet; 6' steel rail with sign - West, 1.0 foot.

igned by John R. Garske

Date 12/12/94

urveyor's Michigan License No. 28410



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983