

MAR 09 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T 43N R 32W	I-13
	T 42N R 32W	I-1 ✓
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD

99 DEC 30 AM 10:12
I.C. Records: L. 8, P. 22
Robert Stiles
REGISTERED DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner Sections 34 and 35, T43N, R32W
Section Corner Sections 3 and 2, T42N, R32W

I, Gary L. Pisoni, in a field survey on April 21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on August 1, 1846 by William A. Burt, U.S. Deputy Surveyor.
Original Corner: Cedar Post
Original Bearing Trees:

Yellow Pine	14"	N 59° E	14 lks (9.24 feet)
Cedar	8"	N 25° W	6 lks (3.96 feet)

On September 21, 1849, Zelotes B. Searls, U.S. Deputy Surveyor established two new bearing trees:

Spruce	16"	S 49° E	26 lks (17.16 feet)
White Birch	10"	S 12° W	16 lks (10.56 feet)

On 10/12/70, Arthur Enger RLS DNR, found a WMPC concrete monument with a brass cap. No evidence of bearing trees. A fence line runs West from the corner position and a fence line runs North from a point 5 feet East of the monument. Monument is stamped as follows: WMPC, T43N, R32W, S-34, S-35, S-3, S-2, T42N, and recorded in Liber 1, Page 7.
1970 Bearing Trees:

Black Spruce	7"	S 11° E	12.7 feet
Tamarack	9"	S 39° W	25.2 feet

PEER GROUP APPROVED
Don Ray Pisoni 12-21-99
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.
On 4/21/99, found the above described monument and the following bearing trees:

Black Spruce	12"	S 07° E	13.15 feet
Tamarack	14"	S 41° W	25.36 feet

I accept the above monument as the best available evidence for restoring the corner position.
Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (all measurements taken to a nail in side of tree)

Black Spruce	8"	N 39° W	19.61 feet
Balsam	8"	N 26° E	6.42 feet
Steel sign post		S 53° E	1.2 feet

99-22
Signed by Gary L. Pisoni Date 12-28-99
Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
No. 27457
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

