

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Iron</u>	Located in:	Corner Code #	
(County)			
1. Public Land Survey	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
2. Property Controlling in Section	S <u>29</u> T <u>42N</u> R <u>32W</u>	_____	12
	S <u>29</u> T <u>42N</u> R <u>32W</u>	_____	13
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

13 Jul 29 2003  
 12 Jul 22 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11				●●									
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**  
 (12-Sec. 29) South 1/16 corner, Section 29. Not established in the original survey.  
 (13-Sec. 29) Southeast 1/16 corner, Section 29. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
 (12-Sec. 29) Established the corner midway and on a straight line between Center of Section 1318.27' North and Quarter corner 1318.27' South.  
 (13-Sec. 29) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 9" twin Maples N35E 47.4' "1/16S BT" 8" twin Maples S33E 25.1'(slope) do 6" Maple N67W 15.6' do 5" Maple N15W 12.8' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 5" R.Pine N21E 79.6' "1/16S BT" 4" R.Pine S68E 33.7' do 5" R.Pine S45E 34.0' do 7" R.Pine S17E 30.3' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
--	---



Signed by Stephan J. Szyszkoski Date 8/6/03  
 Surveyor's Michigan License No. 33986