

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T <u>42N</u> R <u>32W</u>	<u>F10</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>42N</u> R <u>32W</u>	<u>5</u>
	S <u>28</u> T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jan 13 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (F10) Center of Section 28. Not established in the original survey.
- (5-Sec. 28) North 1/16 corner, Section 28. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (F10) Established the corner at the intersection of straight lines connecting opposite 1/4 corners. From the position thus established, I found a 1/2" dia. rebar, projecting 2.7' above ground, not of record, S25E 0.6' distant.
- (5-Sec. 28) Established the corner midway and on a straight line between Center of Section 1316.78' south and Quarter corner 1316.78' north. From the position thus established, I found a 1/2" rebar, projecting 2.5' above ground, not of record, S15W 4.75' distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (F10) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: | (5) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: |
| 12" R.Pine N10W 49.5' "C1/4 BT" | 12" Oak N51E 35.9' "1/16S BT" |
| 7" Oak S37E 45.0' do | 4" R.Pine N82E 17.2' do |
| 10" Oak S26W 10.7' do | 6" Maple S73W 9.6' do |
| 7" R.Pine N70W 39.0' do | 14" Oak N32W 14.2' do |
| Set a sq'd oak post adjacent. Bearings are magnetic. Distances are to nail with tag. | Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/9/04

For the Michigan Department of Natural Resources, Office of Land and Facilities